

Annotating and Sketching on 3D Web Models

Thomas Jung, Mark D. Gross, Ellen Yi-Luen Do

Design Machine Group, University of Washington
208 Gould, Box 355720, Seattle, WA 98195-5720, USA
+1 (206) 543 1604

{tjung | mdgross | ellendo}@u.washington.edu

ABSTRACT

This paper reports on our progress and findings in building a Web annotation system for non-immersive 3D virtual environments. Over the last two years, we developed and tested two systems for collaborating designers to comment on virtual 3D models. Our first system, Redliner [12] lets design team members browse and leave text annotations on surfaces in three-dimensional models. Experience with Redliner, including two user evaluations in different settings, led us to develop Space Pen [13], a second annotation system with improved interaction capabilities. It goes beyond the post-it notes metaphor, allowing users to draw in and on the virtual environment.

Keywords

Annotation, Collaboration, 3D models, VRML, sketch in 3D, pen based interface, Java 3D

INTRODUCTION

Collaborating with remote users on a specific work task can be facilitated by web applications for sharing and annotating documents. Architects, among other kinds of designers, produce three dimensional artifacts and work for each project with new partners (clients, contractors, etc). Specifically, web collaboration tools focusing on design activities must facilitate discussion about three-dimensional designs and must be easily navigated by all participants.

Two years ago we began work to address this need. We first created Redliner, a web-based system that enables users to post text annotations on a 3D model. After testing Redliner in design settings we developed a more graphically oriented system called Space Pen for drawing annotations on 3D virtual environments.

Motivations

As architects, we know that design involves more than merely conceiving and drawing a building. Architects work in teams with other participants who review and discuss a design to improve it until all parties are satisfied that it can and should be built. In this process, architects and their teammates exchange a large number of documents and spend a great deal of time meeting to resolve specific design issues. This becomes challenging when a firm, its

contractors, and its clients are distributed around the world. The Guggenheim Museum in Bilbao designed by Frank Gehry is perhaps the best known project out of thousands each year that involve foreign architects on foreign sites. On these jobs much time and money is spent to enable all participants to meet and communicate their ideas. Architects and their clients already take advantage of fax, electronic mail and some capabilities of the Internet. However, tools to communicate design decisions effectively through that network are still immature. The discipline lacks an appropriate way for participants to discuss and record three dimensional design decisions.

Why 3D?

Like practitioners in other disciplines such as chemistry and medicine, architects use 3D artifacts to communicate complex concepts. Architects build 3D physical models at an early stage to clarify their concepts, and at a more advanced stage, to communicate design ideas to other parties. However, physical models are often large, heavy, difficult to modify and they usually present only a building's exterior appearance. Three dimensional computer graphic models are replacing physical models in many aspects of professional practice; therefore, we set out to use these models to support collaborative work and specifically the discussion of artifact-centered design issues.

The rest of the paper is organized as follows. The next section reviews related work on collaborative virtual environments, and annotation. The third section introduces Redliner, our first system for annotating 3D virtual environments by embedding digital post-it notes. The next two sections present two studies using Redliner, which led to Space Pen, presented in the final section, a system in which users can draw proposed changes directly onto the model.

RELATED WORK

Collaborative Virtual Environments (CVE), originally oriented toward entertainment and social interaction, has led to research on tools to facilitate work tasks. Emphasis has been on synchronous collaboration. Typical are ToolSpace [8] and DDRIVE [6] (Distributed Design Review In Virtual Environment), which both aim to support synchronous communication and collaboration in specific work tasks. DDRIVE, developed to support collaboration on car design, supports web audio discussions for review of 2D and 3D artifacts. ToolSpace offers a 3D VRML (Virtual Reality Modeling Language) workspace

*LEAVE BLANK THE LAST 2.5 cm (1") OF THE LEFT
COLUMN ON THE FIRST PAGE FOR THE
COPYRIGHT NOTICE.*

for collaborative work, interaction and discussion through text messaging. In contrast, our Redliner and Space Pen systems support asynchronous discussion through annotation. Asynchronous collaboration avoids scheduling work sessions and also generates a valuable history of discussion and decisions. This asynchronous approach is similar to the voice annotation system in the Virtual Book project [21], which allows users to leave annotation markers in the 3D VRML model and record voice annotations for future retrieval. However, the Redliner system supports text annotations stored on a server as plain text so that semantic search, indexing, or threaded thematic sorting of the text can later be achieved.

Much research has recently focused on digital annotation of text documents. Cadiz and Brush have developed and tested systems for asynchronous collaboration around text documents [2][4]. They conclude that systems for collaborative work should "be unobtrusive but accessible, inform without overwhelming, separate higher and lower priority information for different actors at different times". Marshall underlined the difference between several types of annotations in textbooks and digital libraries [16]. Although Redliner allows only one annotation type (leaving text notes in the model) its successor, Space Pen introduces a second way of commenting on a virtual model by drawing on plane surfaces in the 3D environment.

Loughlin and Hughes [15] introduced the post-it note metaphor to annotate 3D fluid models. Markers associated with text are embedded in a virtual environment and reviewed later by other users. A magic lens filter allows hiding or highlighting markers in a selected area. Adriano and others [22] argued that annotation systems to support learning should take place in 3D virtual space to provide a richer context. Their prototype system proposes allowing users to place grocery shopping lists on a VRML refrigerator door (post-it style) so that relations between annotation and places can be more easily recognized, based on the objects they are attached to. Models shared in Space Pen and Redliner are ordinary VRML models, and our annotation interface is available on any web browser. Craig and Zimring's IDT (Immersive Discussion Tool) [5] is an asynchronous system to annotate architectural 3D models. IDT allows users to leave arrows to designate specific points of the design, circles to annotate larger areas, or geometric representations made of connected cylinders and spheres for simulating 3D artifacts or gestures. Text can be attached to any mark left in the model. However IDT lacks a multiple user interface and wasn't developed to where users could save and retrieve comments.

Products such as Autodesk's Voloview [20] or DrDWG [7] aim at CAD drafters and engineers. They offer reviewing and redlining DWG format files produced with AutoCAD. However, their complex editing interfaces are intended only for professional use and mostly for 2D documents such as floor plans or engineering drawings. Finally, Silicon Graphics' Iris Annotator [11] lets users annotate 3D

models using several media types -- text, audio, video or other 3D models. However, there is no central server where annotated models are saved, and consequently no history or record of design changes.

In our test of the Redliner system (outlined below), navigation in virtual space with a VRML browser emerged as a significant problem. Disorientation is a common effect of navigating 3D virtual environments. In studies on the ease of use of VRML2.0 [3] most users felt lost in the 3D environment and often needed to refer to maps or viewpoint lists to reorient themselves. Several studies examined new ways of navigating into 3D virtual spaces [1][10], but as Burton, Kilgour and Taylor [3] observed, the best navigation interface depends on what kind of 3D virtual space one is browsing and what kind of task is required.

REDLINER : LEAVING POST-IT® NOTES

We began by implementing Redliner [12], a system to annotate 3D models by leaving annotation marks (represented as colored spheres) directly in the 3D representation of a building. Any member of the design team can log on the Redliner Web site, identify a login name and choose an annotation color. The system first presents the history of previously annotated projects as well as any new versions of the design posted by the design team.

The Redliner interface (figure 1) is simple. It can be described in a few sentences and intuitively understood even by novice users. It contains a window with two frames: one containing users' text annotations and the other for 3D interaction with the design model. Comments listed on the left side of the Redliner window are sorted by time and by author. The right side displays the 3D model. (Screen resolution issues preclude embedding the comment text directly into the 3D model.)

Typically, one member of the design team is responsible for producing the design model for review by others. This person also sets up a list of view points in the 3D model window to help visitors to navigate. When a visitor leaves an annotation mark on the model, his virtual location and orientation is saved as a new view point so that future visitors can retrieve and view the comment in the design context in which it was made. After a user finishes annotating the model the system emails other participants to inform them about the new notes.



Figure 1. The Redliner interface: Left: Annotation window lists sorted comments. Right: The 3D interaction window includes four (mode) buttons and the CosmoPlayer navigation bar.

The three mode buttons in the 3D interaction window (Figure 1 right) control different Redliner modes: Annotate, Measure and Navigate. They modify or change mouse events in the 3D window to have different effects on the model. In 'Annotation' mode, mouse clicks leave a colored sphere on the virtual model and open a text-input window. In 'Measure' mode, two consecutive clicks reveal the distance between two selected points. (We added this feature after users complained about difficulties understanding dimensions in the model.) In 'Navigation' mode, clicks and drags inside the 3D view window move the user around the model. The 'Exit' button indicates the session end.

Implementation

Redliner uses the capabilities of certain VRML browsers (CosmoPlayer, Cortona, etc.) to communicate with Java applets via the VRML External Authoring Interface. The Redliner applets watch for events from the 3D window or the mode buttons and respectively activate the **callback** or **actionPerformed** method. The **callback** method displays a new sphere at the location of the click, opens the "measure window" or displays an existing comment according to which mode was selected and where the click occurred. The **actionPerformed** method responds to the mode change or exits the system.

When the visitor clicks on a surface to annotate the model, the system generates a VRML description for the annotation sphere while the applet gathers the text comment in a pop-up window. Once the visitor saves the comment, Java sends the VRML description and the associated text to a server Perl script. The Perl script adds the sphere to the existing VRML model.

TESTING REDLINER

We tested Redliner in two different settings. In the first test, we asked users to annotate a model of their workplace. The annotation took place within the workplace itself, so they could easily relate the virtual and the physical space. The second test involved an architectural project for remodeling an apartment building. There, the space the users were

annotating did not yet exist, so they had to rely entirely on the virtual model.

Test 1: The L3D Laboratory

Our first test took place at the University of Colorado. Students and faculty members at the L3D Center had recently moved into a new laboratory space and were actively discussing how best to inhabit this space. We set up a Redliner workstation inside the L3D lab and asked the group members to annotate a model of their new laboratory space, commenting on the arrangement of workspaces and furniture.

Method

The test was divided into two sessions. In the first session, we videotaped participants using Redliner (alone or in a team of two) to annotate the model. We explained to participants how to move around the model using preset viewpoints or the walking mode of CosmoPlayer and how to view and leave comments. We also gave them a floor plan indicating the location of each preset viewpoint. We provided full technical support during the experiment and each team was given as much time as they wanted to annotate the model. Two cameras recorded users' reactions and discussion. A third view showing the Redliner web window allowed us to keep track of how users were navigating through our system (figure 2). Once they were done reviewing the virtual space, we asked them to comment on the system concepts and usability.



Figure 2. The video setup. Participants were observed (channels 1 and 3) while their annotations were recorded in real time (channel 2).

In the second session, conducted several weeks later, we printed all the comments that users had left on Redliner and stuck them on their real locations in the lab. We invited the same participants to walk around the room and this time to leave physical post-it notes on the walls and furniture. We tried that way to identify the limitations of our system by comparing our computerized system to its physical analog.

Similarly Whittaker and Schwarz [24] identified several limitations of MS-Project™ compared to paper based scheduling of work tasks, such as failure to promote face-to-face communication, decreased awareness of other people's actions and lack of visibility and permanence.



Figure 3. Annotation in the real space. Participants wrote and left post-it notes on walls and furniture.

Figure 3 shows several participants reading post-it notes left on the wall while another writes a comment to be placed on the table she is writing on. Both in the physical and virtual session, some elements of the space generated more discussion than others. For example, a dozen comments were left to discuss the shape and the use of a dividing wall element (figure 4).



Figure 4. Comments left on a dividing wall element. Long strip notes at the top are printed from Redliner; the smaller rectangular ones were posted later in the physical space.

Observations

The eight teams dropped more than 70 comments in Redliner during the week of the experiment. Each team had a different way to use the system. Some teams started by browsing the list of previous teams' comments and clicked on those that looked interesting, to find them in the space and then possibly respond. However, the most common way people used Redliner was to move around the virtual space, clicking on the notes in highly commented area of the model, recognized as the most conflicting arrangements.

We observed the same behavior during the physical annotation experiment. People walked around the room toward places they felt needed to be changed, read the comments related to that part of the room and often left a note describing their opinion. Comments were left more quickly in the second session of the test where users walked around the physical space. In an hour, a total of 53 comments were posted on walls and furniture.

Often, during the first session, users stood up and walked around to gain a better understanding of the physical space before returning to the virtual environment to leave a note. Most participants made extensive use of the 2D floor plan to orient themselves in the virtual environment, and connect their understanding of the virtual space with the physical space.

Navigating through the space from one viewpoint to another obliged the users to discuss and react to every part of the room. In the two-user teams, almost every preset viewpoint initiated a discussion, which usually led the team to drop a comment summarizing their observations.

Some users had difficulty navigating the different Redliner functions. Users often did not understand how to relate the text of a comment to its location in the virtual world. Some felt inhibited from moving from the text display of a comment to its location and they quit before exploring the whole model. At the end of the test, though, the L3D lab model was covered with colored notes (figure 5).




Figure 5. The L3D lab model annotated by several users (right). The list of text comments associated with the spheres in the model (left).

Results

The experiment took place in the space itself. Users were annotating a virtual model of the place they were physically inhabiting. Comments like “we lived in the space long enough already, so the 3D representation is not necessary. 2D would be enough” were common. Most believed that knowing the physical space was a big advantage. However, they also acknowledged that viewing a digital 3D model of a design proposal is comparable to a “model house” that used by real estate agents to help people understand a proposed space.

Some users requested the ability to arrange the space themselves and move objects around, or at least to indicate a desired move by making arrows or sketches. They viewed localized text annotations as a limited way to annotate a space. Some also felt confused when they wanted to comment on an area of the room (rather than an object), on a general characteristic (e.g., the quality of light), or on the absence of something. “Where should I put the note?” was repeatedly asked. Comments such as “We would like to float over the space and see it as a whole to sketch and comment on general concerns” led to our later Space Pen implementation to facilitate 'virtual graffiti' on any place in the model.

Some would like to view several interchangeable space arrangement alternatives in the same model. Therefore we added “layers” functions to Redliner in the next (Strasbourg apartment building) experiment to enable a user to switch on and off different foci or options in the design. Some users said they would like the system to automatically label the annotations with keywords (Redliner supports user input of a title for each comment) and group them according to keywords as well (in addition to the current system’s sorting by time and author)

Participants found that the ability to leave anonymous comments in the physical world and to relate comments with one another enticed them to leave different, often shorter, comments than in the virtual model. Comments such as “Yes”, “I agree”, or “good idea” were not left on Redliner, but appeared often in the physical space. However, users liked the fact that these virtual post-it notes don't fall off the wall and that the system keeps a good record of the history of discussion. Another insight about why we saw fewer notes in the digital world than the physical space (besides the complaint that it's hard to navigate in VRML unless one uses preset viewpoints) is that users were paired in the experiment and they all logged in with their real names. At least one user mentioned that subtle peer pressure was a reason that people took longer to format more coherent and elaborate notes than the spontaneous note leaving we saw in the real world when the note-writers remained anonymous. Therefore, a solution to foster more input could be encouraging anonymous annotation. These users, however won't get the benefits of notification when new annotations are made to the model.

Users suggested that annotation markers could also indicate whether the comment was positive, negative, or neutral.

Some comments left in the physical space also contain drawings describing furniture arrangement. Users wrote in capital letters, bold, or underlined words to add emphasis. Redliner did not offer these options.

Test 2: Apartment Building in Strasbourg

From April to June 1999 we conducted another test using Redliner in the design of an actual architectural project. An architectural team was chosen to remodel an apartment building in the center of Strasbourg. We decided to try using Redliner to support the team in remodeling the top floor apartments. The client possessed a computer at home but had little experience using it. We installed Redliner on the client’s computer and showed him how to use the system. We also added several buttons (Figure 6) to the 3D interaction windows to facilitate turning on or off the display of optional layers showing different design alternatives, or different components of the building (i.e., structure, partitions, wiring, furniture, etc).




Figure 6. First stage of the design: Users could display or hide optional layers in a global representation of the project. (Text annotation frame is not shown).

This test aimed to evaluate the use of Redliner in an ordinary architectural process. To facilitate design decisions, we offered several new features; in particular the possibility for each participant to present and view several design alternatives. Figure 6 shows an example. Participants could view and annotate the design project as a whole in a “semi 3D” format, where they could view the project, but also relate the different floors in 3D.

Findings

As the design progressed, we posted models of the project at different stages. The client and two other participants (of the architectural team) then annotated the models. These two users visited and annotated the model more frequently than the client. The client did attempt to use the system but felt intimidated and finally didn't use it as much as we hoped. The most difficult part to understand was how to operate the CosmoPlayer browser. The basic idea of the Internet and running a program over the network was also a disrupting new concept for the client.

However, the client felt compelled by seeing and walking virtually around his future home. As we demonstrated the system the client began to comment on design issues. Later, although the client did not use Redliner extensively to annotate and communicate with the architectural team, still many questions the client raised during the face-to-face meetings (that we still scheduled) related to perceptions gained by viewing the model in 3D.

Lessons learned

Overall, users were excited about reviewing and annotating a design project in a 3D environment over the Web. Being able to access and comment on the model anytime, anywhere was seen as a great advantage of the Redliner system. One apparent benefit was that the 3D model draws users' attention to details that might elude the user in a 2D representation. A simpler means to navigate the model was also clearly needed: CosmoPlayer was a significant obstacle to using Redliner.

Many users wanted to comment on the general space rather than a local design issue and wondered where to place this annotation. Text annotation was considered limited; users wanted to interact more directly with the space (such as to quickly sketch over a problem area in the model to suggest improvements or additions), and Redliner only offered dropping annotation markers. In the first test, users perceived the system as an interesting collaborating tool but maybe not for design purposes. In the second test, users appreciated the ability to view alternative design options, but still felt frustrated with using just text to propose a design change. Design collaboration requires more than text comments.

In summary, users wanted:

- A simpler means to navigate the model.
- Threaded discussions & better organization of comments.
- A way to apply annotations not only to individual objects, but also to regions of space.
- Interaction with the model beyond text comments – that is, the ability to mark or draw right on the space where you want it.
- The ability to edit or add to the model directly.

We took these findings seriously in our research. Much of the above functionality has since been added to the

Redliner interface and are currently addressed by other projects in our research group. Here, we focus on addressing the users' requests to 'draw in 3D' and implemented a system called Space Pen.

SPACE PEN: DRAWING ON SURFACES

Based on lessons learned from Redliner, we are developing Space Pen [14]. It serves the same goals as Redliner: to give designers better tools to annotate 3D models, but Space Pen employs a pen interface that enables users to sketch design suggestions directly on the model as well as add text annotations. As in Redliner, users can tag the model with notes associated with text comments. Space Pen users can also mark up the surfaces of the 3D model (like writing graffiti) and save those drawing annotations for others to review.

The Space Pen annotation system also builds on work on freehand drawing ('calligraphic') interfaces such as [6] and [23]. We share the position taken by these efforts that the uses of drawing and diagramming should not merely produce graphic imagery, but also can communicate symbolic and spatial information to knowledge based design systems.

Space Pen's support for sketching in 3D relates to other 3D sketching systems that have been principally developed to support the creation of models. For example, Sketch! [22] interprets strokes to create 3D forms. Stilton [19] uses an existing model or photograph as a background and transforms the user's line drawings into geometric 3D objects such as boxes or pyramids. By contrast, in Space Pen, 3D sketching mainly supports annotation rather than modeling. Although our interface could allow users to create new 3D objects, we are more interested in developing a commenting interface for drawing on existing 3D models.

Navigating in a VRML browser was a persistent problem with Redliner. To avoid this, we wrote our own 3D browsing interface in Java3D. We adopted a simpler way of walking through the model using keyboard arrow keys, familiar to users of popular 3D games like Doom or Quake. However, Space Pen still employs VRML for describing 3D scenes, which allows users to create a model using off the shelf modeling software. Space Pen imports the model using the Java 3D library and the vrm197 Java archive. It can import any VRML model and analyze its geometry, enabling users to annotate and draw on its surfaces later on. The Space Pen interface (shown in Figure 7) employs a minimum of graphical user interface widgets: the color selection circles (left) and the 'save' button are currently the only screen widgets used. Other Space Pen functionality is invoked using pen gestures.




Figure 7. Adding a door on a wall. A rectangle drawn on a surface is recognized (echoed in the bottom left text field) and rectified (right).

The ability to draw directly on model surfaces addresses users' desires to annotate the model with more than text comments, and to propose physical design changes in the model space itself. A user can, for example, indicate a new position, dimension, or shape for a window or door just by drawing it on the wall surface (figure 7; left). The drawing mark can also—but need not—be associated with an explanatory text comment.

To address users' needs to post more general comments about a space or a larger part of the model (in addition to commenting on a specific object), we added a “draw in space” feature. A quickly drawn straight line gesture generates a temporary drawing surface directly in front of the user's point of view (figure 8). Drawing marks made on this surface remain as new elements of the model.

Following the work on diagram recognition in two dimensions [9], Space Pen can also recognize drawings that the designer makes on model surfaces. Presently, it's limited to recognizing simple symbols: rectangles, circles, triangles and arrows. Once a symbol is recognized, the system can interpret it in different ways. For example, Space Pen can rectify a crudely drawn figure, or execute a command based on the graphical symbol. In figure 7 (right) the rectangle drawn on a wall to indicate a door has been automatically rectified and filled with another color, giving a more realistic appearance of a door.

Space Pen could -- in a future version -- augment interaction by providing predefined object behavior from sketches like moving the sketchy widget on the interface design in the SILK system [26]. The current version of Space Pen already performs recognition of freehand sketches in the 3D space and can use this recognition to trigger actions on the drawn object. We saw that the user can draw a rectangle to annotate the model with a door. Space Pen also recognizes the surface the rectangle has been drawn on. We are working on getting Space Pen to make a further inference beyond simply creating the door geometry, for example, linking the newly created object to a product database and adding additional behaviors for it to perform (e.g., a 3D door that opens and closes). In the same way, the system already interprets an arrow as a command and we are working on interactively uploading and

downloading the object models and managing version control on the server.




Figure 8. Drawing annotations in space. Drawing a quick straight line on an existing surface generates a temporary grid plane (left) for a user to draw general comments about the whole space. The bright square below the house indicates a text note left to complement the drawing annotations.

We plan to add 2D “you are here” maps and viewpoint lists to Space Pen. The viewpoint list was valuable and notably was used by all participants in the Redliner experiment. It is still the best way to retrieve comments that are dispersed around a large model. In addition, we plan to add more sophisticated means to search and manage the text comments; e.g., support for a threaded discussion that references specific locations in the model, and indications of positive and negative comments.

CONCLUSION

This paper described our efforts to create an intuitive collaborative system for annotating and reviewing 3D models on the Internet. We aim to develop a system that anybody can use, architects as well as non-designers, computer experts as well as novices. Space Pen, at its early stage of development, already improves annotation in 3D environments over Redliner by allowing different kind of annotations.

Although our research focuses on designers and architects' issues, we believe that other disciplines that reference physical structures, such as chemistry, engineering, mathematics, and especially education, could benefit from web based 3D drawing annotation.

ACKNOWLEDGMENTS

This research was supported in part by the National Science Foundation under Grants No. IIS-96-19856 and IIS-00-96138. The views contained in this material are those of the authors and do not necessarily reflect the views of the National Science Foundation. The authors thank the L3D Lab in University of Colorado at Boulder (especially Leysia Palen and Gabriel Johnson) and the CRAI (Centre de Recherche en Architecture et Ingénierie) in Nancy, France, for their help, comments and feedback during the experimentation phases. The L3D lab model was built in

VRML by Jimmy Davidson. Ronald Ygon and Michael Wells designed and modeled the Internet Café.

REFERENCES

1. Ballegooij (van) A., Eliëns A., 2001, Navigation by Query in Virtual Worlds, *Proceedings of the 3D Technologies for the World Wide Web 2001*, pp.77-83
2. Bernheim Brush A.J., Barger D., Gupta A., Cadiz JJ, 2001, Robust Annotation Positioning in Digital Documents, *Proceedings of the SIG-CHI Conference on Human Factors in Computing Systems*, Seattle, April 2001, pp. 285-292
3. Burton N, Kilgour A C and Taylor H, A Case Study in the Use of VRML 2.0 for Marketing a Product, *Proceedings of From Desk-Top to Web-Top: Virtual Environments on the Internet, World Wide Web and Networks, International Conference*, Bradford, April 1997, pp. 1-24.
4. Cadiz JJ., Gupta A., Grudin J., 2000, Using Web Annotation for Asynchronous Collaboration Around Documents, *Proceedings on the ACM 2000 Conference on CSCW*, December 2-6 2000, Philadelphia, PA, USA, pp309-318
5. Craig, D. L. and Zimring, C., 1999, Support for Collaborative Design Reasoning In Shared Virtual Spaces, *Media and Design Process, Proceedings of ACADIA '99*, Salt Lake City, p.126-137
6. Daily M., Howard M., Jerald J., Lee C., Martin K., McInnes D. and Tinker P., Distributed Design Review In virtual Environments, *Proceedings of the third international conference on Collaborative Virtual Environments*, 2000, Pages 57 - 63
7. Dr DWG, <http://www.drldwg.com/>
8. Goddard T., Sunderam V. S., 1999, ToolSpace: Web Based 3D Collaboration, *Proceedings of the 1999 International Conference on Intelligent User Interfaces*, January 5-8, 1999, Redondo Beach, CA, USA, pp. 161-165
9. Gross, M.D. and Do, E.Y., Drawing on the Back of an Envelope: a framework for interacting with application programs by freehand drawing, *Computers and Graphics* **24**(2000) 835-849.
10. Hanson A. J., Wernert E. A., 1997, Constrained 3D Navigation with 2D Controllers, *Proceedings of the Conference on Visualisation '97*, pp. 175-183
11. Iris Annotator: <http://www.sgi.com/software/annotator/>
12. Jung, T, Do, E.Y, and Gross, M D., 1999, Immersive Redlining and Annotation of 3D Design Models on the Web, *Proceedings of the Eighth International Conference on Computer Aided Architectural Design Futures*, p. 81-98. Kluwer
13. Jung, T., Gross, M.D. and Do, E.Y.(2001), Space Pen: Annotation and Sketching on 3D Models on the Internet, *Proceedings of the 9th International Conference on Computer Aided Architectural Design Futures*, Kluwer Academic Publishers. pp. 257-270
14. Loughlin M. M. , Hughes J. F., 1994, An Annotation System for 3D Fluid Flow Visualisation, *Proceedings of the Conference on Visualisation '94*, IEEE, 17-21 October 1994, pp. 273-279
15. Marshall C., 1997, Annotation: from paper books to the digital library, *Proceedings of the 2nd ACM International Conference on digital Libraries*, 1997, pp. 131-140
16. Tan D.S., Robertson G.G., Czerwinski M., Exploring 3D Navigation: Combining Speed-coupled Flying with Orbiting, *Proceedings of the SIG-CHI Conference on Human Factors in computing Systems*, Seattle, 2001, pp.418-425
17. Turner A., Chapman D., Penn A., 1999, Sketching a Virtual Environment: Modeling Using Line-Drawing Interpretation, *Proceedings of the ACM Symposium on Virtual Reality Software and Technology*, 1999, pp. 155-161
18. VoloView, <http://www3.autodesk.com/adsk/index/0,,224835-123112,00.html>
19. Whittaker S., Schwarz H., 1995, Back to the future: pen and paper technology supports complex group coordination, *Conference Proceedings on Human Factor in Computing Systems*, 1995, pp. 495-502
20. Zeleznik R. C., Herndon K. P., Hughes J. F., 1996, SKETCH: an Interface for Sketching 3D Scenes, *Proceedings of the 23rd Annual Conference on Computer Graphics*, 1996, pp.163-170
21. Jouke C. Verlinden; Jay David Bolter; Charles van der Mast. "Virtual Annotation: Verbal Communication in Virtual Reality". In *Proceedings of the European Simulation Symposium 1993 (ESS'93, Delft 25-28 october)*.
22. Christian M. Adriano, Alberto B. Raposo, Ivan L. M. Ricarte, Leo P Magalhaes, Changing interaction paradigms in annotation environments, *EDMEDIA 2000*, Montreal, Canada
23. James A. Landay and Brad A. Myers, "Sketching Interfaces: Toward More Human Interface Design." *IEEE Computer*, vol. 34, no. 3, March 2001, pp. 56-64.
24. James A. Landay, Interactive Sketching for the Early Stages of User Interface Design. Ph.D. dissertation, Carnegie Mellon University, Pittsburgh, PA. December, 1999